



PROJECT:

Gray Army Airfield UST Removal

Cherokee Construction Services was contracted as the **prime contractor** to decommission and remove a 12,000 gallon UST located at the Gray Army Airfield located on Fort Lewis, Washington. The UST was removed in accordance with applicable Washington State and US Environmental Protection Agency Regulations.

The UST was formerly utilized by the Fort Lewis Flying Club and was located within the Gray Army Airfield boundary. The location of the UST required additional health and safety measures to be implemented to ensure completed compliance with Gray Army Airfield policies. Cherokee Construction Services personnel and their subcontractors completed Gray Army Airfield safety training and testing prior to performing the UST decommissioning.

Cherokee Construction personnel, licensed by the International Code Council as UST Decommissioners, inerted and triple rinsed the UST in accordance with all applicable laws and standards. The UST and excavation were sampled by a third party consultant acting as a registered Washington State Site Assessor.

The UST was removed in a manner that allowed normal operations to continue at Gray Army Airfield. The UST excavation area was restored to match the original grade and revegetated. The UST was removed on an expedited schedule.

Cherokee Construction Services completed the UST decommissioning ahead of schedule and within the proposed budget.

Project Highlights:

- Removal of UST From Active Army Airfield
- Work Performed in Accordance with Military & FAA Regulations
- Expedited Project Schedule

Project Vitals:

- **Client:** US Army Corps of Engineers, Seattle District
- **Location:** Fort Lewis, Washington
- **Contract Amount:** \$91,863.00
- **Duration:** May 2009 – September 2009
- **Contract #:** W912DW-08-D-1017
- **Amount Self-Performed:** 76%
- **NAICS Code:** 562910

